

Id	Description	Phase
1	Support service time	Take out
2	Shutdown	Take out
3	Process Isolation	Take out
4	Depressurization	Take out
5	Cool down	Take out
6	Electrical Isolation	Take out
7	Draining	Take out
8	Purging	Take out
9	Line Emptying	Take out
10	Blinding	Take out
11	Ventilation	Take out
12	Washing	Take out
13	Item Removal	Take out
14	Item conveyance to workshop	Take out
15	Item conveyance from workshop	Bring in
16	Reinstalling	Bring in
17	Leak test	Bring in
18	Air Removal	Bring in
19	Commissioning & Start up	Bring in